

### YOU are the Jury!!

- Here in person at BIMForum | San Antonio
- Online at AIA TAP Webinar
- Selection of Professionals' Choice will be Immediately After these Presentations
- Take Notes and Be Prepared to VOTE!



### BIMFORUM





Ed Gannon Manager of Design Services

The Pennsylvania State University

Gene Herring Associate Director

University of Florida Facilities Planning and Construction

Patrick Wilson Project Manager

University of Chicago

# 2012 COAA | AIA Owners' Choice BIM Awards Jury

To be Presented at COAA's 2012 Spring Owners' Leadership Conference | Dallas Texas | May 10 2012

### Your Moderator and Hosts from AIA

- Stephen Hagan FAIA
- Calvin Kam AIA PhD
- Tony Rinella Assoc AIA
- David Scheer AIA
  - 2012 Chair of AIA TAP

### Session | Online Webinar Learning Objectives

- Learn and discover award winning team dynamics, the people and process side of BIM and its influence on architectural practice
- Identify what BIM is, and what its future could be, based on lessons learned from eight years of AIA TAP BIM awards
- Recognize how sustainability can be enhanced and enabled using BIM
- Identify the interface between BIM and Integrated
   Project Delivery (IPD) and Process Improvement

### Online Webinar Information



www.aia.org FAQ Add a New Discussion Post Contact Us

Login to Contribute



Wednesday, April 25, 2012, 4:30 PM - 6:00 PM

This session is co-sponsored by BIMForum, COAA and AIA TAP. It will present the five AIA TAP 2012 BIM Award winners in Category B (Process Innovation Using BIM), competing for the 2012 Professionals' Choice BIM Award. Following presentations by each of the teams, both online webinar attendees as well as those in attendance in San Antonio real-time, will vote for the Professionals' Choice BIM Award winner.

The winner will be announced at **6:30pm ET** (immediately following the webinar). Find out the winner by following @AIA\_TAP on Twitter and engage in the conversation by using #AIATAP.



### Attendees will earn 1.00 CEH

\*Note the webinar will be open 15 minutes prior for accessing the site and logistics, so that the webinar can begin at 3:30pm CT Sharp.



### Learning Objectives

- Learn and discover award winning team dynamics, the people and process side of BIM and its influence on architectural practice.
- 2. Identify what BIM is, and what its future could be, based on lessons learned from eight years of AIA TAP BIM awards
- 3. Recognize how sustainability can be enhanced and enabled using BIM
- 4. Identify the interface between BIM and Integrated Project Delivery (IPD) and Process Improvement

### BIMFORUM



Martin Fischer PhD Jury Chair

Stanford CIFE Palo Alto, CA

Boyd Black Assistant VP Capital Project Delivery

University of Chicago Chicago, IL

Peggy Deamer PhD Professor

Yale School of Architecture New Haven, CT Roger Grant CSI, CDT Program Director

NIBS Washington DC Dan Russell, CM-BIM Leed AP

Sundt Construction Phoenix, AR

# 2012 AIA TAP BIM Awards Jury

Presented at 2012 AIA Convention BIM Awards Reception and Ceremony | Washington DC | May 16 2012

# 2012 BIMForum Professionals Choice BIM Award



### 5 Finalists for Professionals' Choice Award

- Alta Bates Summit Medical Center
- Edith Green-Wendell Wyatt Federal Building Modernization
- Institute for Systems Biology
- Maricopa County South Court Tower
- Warrior in Transition Barracks

## BIMFORUM



## **Alta Bates Summit Medical Center**


Presented by

Dudley Campbell AIA, LEED AP Devenney Group Ltd., Architects




Devenney Group, Ltd., Architects

**DPR** Construction



Alta Bates Summit Medical Center – Patient Care Pavilion

Aerial Rendering



Alta Bates Summit Medical Center – Patient Care Pavilion

Aerial Rendering



Alta Bates Summit Medical Center – Patient Care Pavilion

**Building Entry** 




Alta Bates Summit Medical Center – Patient Care Pavilion

**Building Entry** 



Alta Bates Summit Medical Center – Patient Care Pavilion

Patient Room Concept Rendering



Alta Bates Summit Medical Center – Patient Care Pavilion

Patient Room Concept Rendering




Alta Bates Summit Medical Center – Patient Care Pavilion

Lobby Concept Rendering



Alta Bates Summit Medical Center – Patient Care Pavilion

Nurse Station Concept Rendering



Alta Bates Summit Medical Center – Patient Care Pavilion

Elevator Lobby Concept Rendering




Alta Bates Summit Medical Center – Patient Care Pavilion

Family Waiting Room Concept Rendering



Alta Bates Summit Medical Center – Patient Care Pavilion

Computer Composite – BIM Model with Skin Rendering



Alta Bates Summit Medical Center – Patient Care Pavilion

Photo Composite – Photograph with BIM Overlay













Process Mapping
Constructability Reviews
Model for Fabrication

110 Users42 Unique Companies3,055 Completed Tasks

**Project Process** 


Commitment Based Planning















What we modeled
What we didn't model
Difference between interior and exterior

Modeling - Design/Pre-Construction

Alta Bates Summit Medical Center – Patient Care Pavilion

What was modeled



Modeling for Fabrication

Alta Bates Summit Medical Center – Patient Care Pavilion

**Rebar Coordination** 

# Clash Free Mode



### **Clash Detection**


Alta Bates Summit Medical Center – Patient Care Pavilion

Goal: Clash Free Model

				-																			
Min Clearances in Inches	Medium Pressure Supply	Low Pressure Supply	Exhaust Duct	Flex Duct	VAV Boxes and HeatCraft Coils	Fire Sprinkler piping	Hydronic Piping	DCW Piping	DHW Piping	Med Gas Piping	Waste Piping	Vent Piping	Rain Wate Leaders	Conduits	Hangers	J Hooks	Misc Metals	Wall Bracing	King Studs for Doors/Drywall	Struct Steel	Seismic Bracing	Hangers	Access Zones
Fire Sprinkler Piping	1	1	1	1	1	X																	
Hydronic piping	1	1	1	1	1	1	Х																
DCW Piping	1	1	1	1	1	1	1	X															
DHW Piping	1	1	1	1	1	1	1	1	Х														
Med Gas Piping	2	2	2	2	2	2	2	2	2	X													
Waste Piping	1	1	1	1	1	1	1	1	1	1	X												
Vent Piping	1	1	1	1	1	1	1	1	1	1	1	X											
Rain Water Leaders	1	1	1	1	1	1	1	1	1	1	1	1	X										
Conduits	0	0	0	0	0	1	1	1	1	2	1	1	1	X									
Hangers	2	2	2	2	2	2	2	2	2	2	1	1	1	2	X								
J hooks (Actual)	2	2	2	2	2	2	2	2	2	2	1	1	1	2	2	X							
Misc Metals	1	1	1	1	1	1	1	1	1	2	1	1	1	0	2	2	X						
Wall Bracing	1	1	1	1	1	1	1	1	1	2	1	1	1	0	2	2	1	X					
King Studs for Doors	1	1	1	1	1	1	1	1	1	2	1	1	1	0	2	2	1	1	Х				
Struct Steel	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	X			
Seismic Bracing	1	1	1	1	1	1	1	1	1	2	1	1	1	0	2	2	1	1	1	2	X		
Hangers						1	1	1	1	2	1	1	1	0	2	2	1	1	1	2	1	X	
Access Zones						0	0	0	0	0	0	0	0	0	0	0	0	0	0	2	1	1	X


**Clash Detection** 

Designated Tolerances



**Clash Detection** 

**Designated Tolerances** 




What we tried first...
And Why we **FAILED** 

**Clash Detection** 

Alta Bates Summit Medical Center – Patient Care Pavilion


Successes and Failures





What we did next...
And how we measured **SUCCESS** 

**Clash Detection** 

Successes and Failures








Modeling Effort (above and beyond) Required: (\$100/Hour) x 100 Hours = \$10,000

Early Metrics

Measuring what it's worth



Top 16 Clashes Analyzed In 5 Separate Clash Batches

**Early Metrics** 

Alta Bates Summit Medical Center - Patient Care Pavilion

Measuring what it's worth

Category	Item	Cost	Quantity	ROI
Halfen vs Steel/MEPF	Halfen vs Steel issue	\$1,500	310	\$465,000
Halfen vs Steel/MEPF	Halfen vs MEPF	\$1,100	5	\$5,500
Total				\$470,500
	006-DGL/DEG/CDC - Steel penetrating curtainwall			
Curtainwall/Storefront vs Steel	at cut, roof level.	\$25,000	1	\$25,000
	001-DGL/DEG global issue - steel clash with			
Curatinwall/Storefront vs Steel	curtainwall at cut.	\$25,000	6	\$150,000
	002-DGL/CDC/DEG - Slope wall clash btw steel			
Curatinwall/Storefront vs Steel	and mullons	\$50,000	1	\$50,000
	005- DGL/CDC provide detail for cantilevered			
	steel and curtainwall penetration at canopy,			
Curatinwall/Storefront vs Steel	typical.	\$15,000	1	\$15,000
Curatinwall/Storefront vs Steel	007-Steel Clash with storefront	\$20,000	1	\$20,000
Curatinwall/Storefront vs Steel	008-Steel Clash with storefront	\$20,000	1	\$20,000
Curatinwall/Storefront vs Steel	009-Steel Clash with storefront	\$10,000	1	\$10,000
Curatinwall/Storefront vs Steel	010-Steel Clash with storefront	\$10,000	1	\$10,000
Total				\$300,000
	001-Centria panel not needed in interior of			
	snorkel. Make the interior of snorkel shaftwall.			
	Carmel to provide credit for reduction of			
ExWall (Unistack) vs Steel	Unistack scope.	\$25,000	1	\$25,000
	003-A1/DEG/CAS/DGL - how does this unistack			
	attach to the steel? Detail 1/ AY-107CE shows			
	embeds, there is no slab in this area. Need			
ExWall (Unistack) vs Steel	attachment detail.	\$40,000	1	\$40,000
, , ,				
	005-Why is there steel in the unistack wall? Does			
ExWall (Unistack) vs Steel	this wall need to shift out? How it supported?	\$250,000	1	\$250,000
•		•		
	007-How is this centria panel supported? How			
	are all centria panels below L2 supported. There			
ExWall (Unistack) vs Steel	are no AY drawings for below level 2.	\$20,000	1	\$20,000
Total	<u> </u>			\$335,000
ExWall (Unistack) vs MEPF	Penetrations	\$350	350	\$122,500
Total		,		\$122,500
Slab Edge vs Curtainwall/Storefront	001- Mullion clash with slab edge	\$63,000	1	\$63,000
Total		o ■ complete to a ■ Destroy and Self Self		\$63,000
			Total	\$1,291,000

**Early Metrics** 

Measuring what it's worth

- The Coordination Effort Paid for Itself
- Ownership of Project "Skin in the Game"
- Unprecedented Body of Knowledge
- Team Members that Provide Value
- 3d Capable Most Effective
- Submittal vs. Construction
- Too Many Fingers in the Pot
- Permitted and Built from 2d Drawings
- Closer Location = Closer Collaboration

#### Demolition Time Lapse:

http://www.youtube.com/watch?v=MkjNqUevL94

#### 4DScheduling:

http://www.youtube.com/watch?v=RriV1PuMmAU

#### Project Fly Thru:

http://www.youtube.com/watch?v=eJOuKdKKRqg

### Questions?

**Additional Media** 

Fun Videos

### BIMFORUM



### **Alta Bates Summit Medical Center**

Presented by

Dudley Campbell AIA, LEED AP Devenney Group Ltd., Architects

### BIMFORUM



# Edith Green-Wendell Wyatt Federal Building Modernization

Presented by

Jim Riley, Sera Architects

# EDITH GREEN WENDELL WYATT

**FEDERAL BUILDING** 

BIM FORUM APRIL 24, 2012





## RECOVERY ACT MODERNIZATION PROJECT









Transform a 525,421 square foot, 18-story, 1974 office building into a LEED Platinum cornerstone of GSA's green building portfolio.

BUDGET: \$ 141,000,000

#### **MODERNIZATION GOALS**









#### **UPGRADE BUILDING SYSTEMS**

- Seismic upgrade.
- New mechanical, electrical, voice data telecom systems.
- New fire and smoke control system.
- New plumbing system with low flow fixtures for water conservation.

#### **UPDATE WORK ENVIRONMENT**

- Optically advanced electric lighting systems.
- Optimized daylighting.
- Improved indoor air quality.


#### **IMPROVE ACCESSIBILITY**

- New code compliant egress stairs.
- Accessible entries and rest rooms.
- Modern, energy efficient elevators.
- Revised site layout and new landscaping.


### MINIMUM PERFORMANCE CRITERIA ARRA and EISA

Water Conservation **Energy Star Energy Conservation LEED** Requirements Requirements Requirements Requirements 20% Indoor potable Score goal: 97 55% Fossil fuel **Gold Required** water reduction reduction **Platinum Goal 50%** Outdoor potable 30% Energy usage water reduction reduction 30% Solar thermal **ENERGY STAR** 

#### **ENERGY GOAL**



### TENANT ENGAGEMENT ENERGY CONSERVATION MEASURES




#### POTENTIAL ENERGY SAVINGS

Without Tenant ECMS

#### **ENERGY SAVING GOAL**

With Tenant ECMS

## PROJECT DELIVERY METHODOLOGY



*i*-DELIVERY **GSA STANDARD (P-100) VS. INTEGRATED** P100 BIDDING **EST. SAVINGS** \$940,000 44,000 HRS in 15 MONTHS VS. 53,000 HRS in 24 MONTHS FOR PROJECT DOCUMENT PRODUCTION DESIGN EFFORT CONSTRUCTION START 21 - 24 MONTHS 14 MONTHS TIME

### COLLOCATION BENEFITS

#### BETTER COMMUNICATION

- Highly coordinated overall design.
- Fewer assumptions made by disconnected design team members.
- More spontaneous design coordination discussions.
- Better understanding of other disciplines' work flows and design problems.

#### LESS WASTED TIME

 Less time spent waiting for answers from email and voicemail.

EGWW saved an estimated **\$82,000** in travel time to meetings for consultants who were collocated.





#### BIM BENEFITS

#### **BETTER BUILDINGS**

- Better cost certainty
- Enhanced AE coordination & QC
- Ability to generate more visualizations for client comprehension
- Models become collaborative tools for problem solving across disciplines
- Early identification of system clashes before they get out into the field


#### LESS WASTE

Minimizes redundancy



6 REVIT MODELS, 2 CAD DISCIPLINES OVER 30 SOFTWARE PROGRAMS 28 ARCHITECTS, ENGINEERS AND MODELERS

SITE STUDY




1. Numerous daylight studies were conducted to determine the limitations and opportunities available for the project

Shaded Area

March / September


June

December



2. Daylight optimization study first established the size and position of the shading devices and light reflectors. This engineering analysis occurred prior to design architect commencing work.


#### **DESIGN**



3. The design architect began work, translating the engineering criteria to architectural form

**DETAIL MODELING** 

#### **VALIDATION**



4. Budget constrains further refined the form, substituting vertical reeds for the solid vertical shades.

5. the final design was then refined to verify all criteria are met.

glazing to wall ratio

low infiltration rate

super insulated wall

#### **DETAILING**

6. Detailing and shop drawing process commenced with model used for coordination review and detailing refinement.


#### CONSTRUCTION




### BIM CLASH DETECTION

#### **DESIGN-SIDE CLASH ANALYSIS**

CONTINUOUS IMPROVEMENT: As model complexity increases, number of clashes decreases





**Basement corridor model** 



**Basement corridor installed** 


# **BIM** CLASH DETECTION




### BIM TIME AND COST SAVINGS

#### TIME & COST SAVINGS THROUGH PREFABRICATION

MECHANICAL SYSTEMS "MODULAR SKIDS" PREFAB METHOD




ON-SITE FAB. HOURS IN 40-HR WEEK



EQUIVALENT USING PRE-FAB METHODS

38% REDUCTION IN FABRICATION TIME







# **BIM** VISUALIZATION









### BIM CONSTRUCTION AND POST OCCUPANCY


- Quantity Takeoff for Cost Estimating
- Virtual Huddle
- 4-D Scheduling
- Project Phase Planning, Site Logistics
- Laser Scanning and Model Adjustments
- Operations and Maintenance







# **BIM**Sequence clash detection






# **BIM**Construction Completion



View west towards Exit and Security

#### **BIM**

#### **Operations & Maintenance**



Controls diagram for AHU2 with data collection points

### EDITH GREEN WENDELL WYATT FEDERAL BUILDING THANK YOU



### BIMFORUM



# Edith Green-Wendell Wyatt Federal Building Modernization

Presented by

Jim Riley, Sera Architects

### BIMFORUM



### **Institute for Systems Biology**

Presented by

Andrew Marsters and Justin Porter | BNBuilders



### Project Highlights

- Lab "Tenant Improvement" for non-profit research institute
  - GMP delivery, completed in 2011
  - \$12M
  - 90,000 sf in 4-story shell
  - 8 mo construction schedule, 14 mo total project schedule
- Program
  - Labs and vivarium
  - Lab support spaces
  - Core facilities
  - Open offices
  - Office support spaces: conference rooms, coffee bars, informal break-out spaces
- Goals/Considerations
  - LEED CI Platinum
  - Preserve much of existing lab support spaces, conference rooms, offices
  - Extensive reuse of doors, windows, ceiling grid, lighting
  - Significant MEP system replacement
  - Systems integrating/fitting around remaining systems for remaining 2<sup>nd</sup> floor tenant
- Design Intent
  - Inviting, fun, and open work environment
  - Light, vibrant, bold color palette and environmental graphics reflecting tenant's brand
  - Feature stairs as focal point of project

INSTITUTE FOR SYSTEMS
BIOLOGY

2012 AIA TAP / BIM AWARDS




### ARCHITECT'S STATEMENT

- Used Revit and shared model with contractor
- Tools allowed rapid adaptation to changing program while maintaining design intent
- Custom Revit
   "families" aided
   coordination and
   documentation



### CONTRACTOR'S STATEMENT


- Leveraged BIM in nearly every aspect of the project
- Free exchange of model source data between all parties ensured the most accurate, reliable documentation of design intent
- Strong emphasis on collaboration and innovation




#### OWNER'S STATEMENT

- Goal to leverage
   BIM to generate
   and manage
   lifecycle data
  - Design
  - Construction
  - Facilities management
- Accelerated the schedule, pushed the team to enable rapid, accurate, and confident decision-making
- Integrating handover model with facilities management system

INSTITUTE FOR SYSTEMS BIOLOGY 2012 AIA TAP/ BIM AWARDS THE TEAM READILY EMBRACED INNOVATIVE PROCESSES AND TOOLS ACROSS THE ENTIRE PROJECT LIFE CYCLE




#### INFORMATION EXCHANGES



THROUGHOUT
THE ENTIRE
PROJECT THE BIM
WAS UPDATED
CONTINUOUSLY BY
THE PROJECT TEAM



#### **REAL-TIME VISUALIZATION**




# DESIGN AUTHORING & VISUALIZATION

- Parametric capabilities and "design options" in Revit allowed design team to adapt to changing program
  - Parametric families for lab equipment and "lightsaber" light fixtures to track and locate 100's of types
- Real-time, stereoscopic 3-D walkthrough to 300+ people at off-site staff retreat



#### MEP CLASH DETECTION




### 2 SYSTEM COORDINATION


- Coordination of MEP systems vital to complex nature of lab TI
- Intense coordination led to direct reduction of total number of RFIs

THE PROJECT
TEAM WAS ABLE
TO DETECT
AND RESOLVE
NEARLY 2000
CLASHES
BEFORE
CONSTRUCTION
STARTED

INSTITUTE FOR SYSTEMS BIOLOGY 2012 AIA TAP/ BIM AWARDS



#### QUANTITY TAKE-OFFS - STAINED CONCRETE



GROUND LEVEL	Counter Top w Sink Hole: 7"	1	2.67	5.67	2.5	14.175
LEVEL 04	Counter Top w Sink Hole: 7'	1	2.67	- 5	2.5	15
GROUND LEVEL	Counter Top: 61	1		- 6	2.5	15
LEVEL OB	Counter Top_no backsplash: 30" deep	1	. 3	6.5	2.5	16.25
LEVEL 03	Counter Top_no backsplash: 30" deep	1 1	- 3	6.5	2.5	16.25
LEVEL 04	Counter Top_no backsplash: 21" deep	1	. 3	9.5	1.75	15.625
LEVEL 04	Counter Top_no backsplash: 6'	1	. 3	7.6	2.5	19
GROUND LEVEL	Counter Top: 6'	1	3	7.9	2.5	19.75
LÉVEL 03	Counter Top_no backsplash; 6'	1	- 3	8.22	2.5	20.55
EVEL 03	Counter Top: 6"	1	. 3	8.25	2.5	20,625
LEVEL 03	Counter Top: 10'	1	3	9.15	2.5	22.9
EVEL OS	Counter Top_no backsplash: 30" deep	1	. 3	9.17	2.5	22.925
GROUND LEVEL	Counter Top: 6'	1	3	9.5	2.5	23.75
LEVEL 04	Counter Top_no backsplash: 10"	1	. 3	10	2.5	25
EVEL 03	Counter Top: 10'	- 1	3	10.43	2.5	25.075
EVEL 03	Counter Top: 6'	1	3	11	2.5	27.5
EVEL 03	Counter Top_no backsplash: 6"	1	- 3	11	2.5	27.5
EVEL 03	Counter Top: 6"	- 1	3	11.75	2.5	29.375
LEVEL 04	Counter Top w Sink Hale: 7'	1	2.67	11.78	2.5	29.45
LEVEL 03	Counter Top: 6"	1	3	11.78	2.5	29.45
LEVEL 03	Counter Top-Island: 10'	- 1	3.08	- 6	- 5	30
EVEL O'S	Counter Top-Island: 10"	1	3.08	- 6	. 5	30
EVEL 03	Counter Top-Island: 10'	1	3.08	- 6	- 5	30
EVEL 03	Counter Top-Island: 10'	- 1	3.08	- 6	5	30
EVEL 04	Counter Top: PROTEOMICS	1	3	12.52	2.79	34.9308
EVEL 03	Counter Top w Sink Hole: 7'	1	2.67	14	2.5	35
EVEL 04	Counter Top w Sink Hole: 7°	1	2.67	14.11	2.5	35.275
GROUND LEVEL	Counter Top_no backsplash: 24° deep	1	3	3.8	- 2	36
EVEL 03	Counter Top w Sink Hole: 7'	1	2.67	14.47	2.5	36.175
LEVEL 04	Counter Top-Island: 30'	1	3.08	9.92	- 5	49.6
LEVEL 04	Counter Top: 6'	- 1	3	20.59	2.5	51,475
LEVEL 04	Counter Top-Island: 10'	1	3.08	20.44	- 5	52.2
EVEL 04	Counter Top-Island: 10'	1	3.08	10.44	- 5	52.2
LEVEL 04	Counter Top-Island: 10'	- 3	3.08	10.44	- 5	52.2
LEVEL 04	Counter Top-Island: 10'	1	3.08	12.94	- 5	64.7
LEVEL 04	Counter Top-Island: 10'	1	3.08	12.94	- 5	64.7
LEVEL 04	Counter Top-Island: 10'	1	3.08	12.94	5	64.7
LEVEL 04	Counter Top: PROTEOMICS	1	. 3	27.5	2.79	76.725
LEVEL 04	Counter Top: PROTEOMICS	1	- 3	27.5	2.79	76.725
LEVEL 04	Counter Top: PROTEOMICS	1	3	27.5	2.79	76,725
LEVEL 04	Counter Top-Island: 10'	- 3	3.08	28	- 5	140
LEVEL 04	Counter Top-Island: 10"	1	3.08	28		140
EVEL 04	Counter Top-Island: 10'	1	3.08	28	5	140
EVEL 04	Counter Top-Island: 10'	1	3.08	28	- 5	140
LEVEL 04	Counter Top-Island: 10'	- 1	3.08	28	5	140
EVEL 04	Counter Top-Island: 10'	- 1	3.08	28	- 5	140
LEVEL 04	Counter Top-Island: 10'	1	3.08	28	- 5	140
						5713.1
	A.					- AAAA

LEED DOCUMENTATION

### 3 QUANTITY TAKE-OFFS

- Material schedules and custom views
- Submit estimate options to client in half the time


### LEED DOCUMENTATION


1 2.67 5.67 2.5 14.175


- LEED "Building Reuse" Credit
  - Significant documentation of reused walls, ceilings, doors, casework
- Revit phases and filters to generate custom views and schedules
- Complete QTO in just two hours, compared to days or weeks by hand

INSTITUTE FOR SYSTEMS BIOLOGY 2012 AIA TAP/ BIM AWARDS









### 4 SHOP DRAWINGS

- Model-based shop "drawings" allowed efficient review and comments
- Fabricators
  automated
  details, takeoffs,
  and drawings
  from the model

MODELING
THE DETAILS
HELPED CUT
THE REVIEW
PROCESS
TIME BY AS
MUCH AS 50%



Drop soffit framing over cage wash coordination

SSTL wall angle to cover gap between


cage wash and GWB header?

#### 5 CONSTRUCTABILITY REVIEW

- SketchUp model as collaboration tool to clarify design intent
- Detail and visualize the "enclosure" around cage-rack washer rooms

WE WERE ABLE
TO FINALIZE
UNRESOLVED
MATERIAL
TRANSITIONS,
WHICH KEPT
CONSTRUCTION
MOVING
FORWARD


INSTITUTE FOR SYSTEMS BIOLOGY 2012 AIA TAP/ BIM AWARDS



"LIGHT-SABER" FIXTURES - CUSTOM LAYOUT DRAWINGS

#### 6 LAYOUT DRAWINGS

- Vivarium to be turned over one month sooner than planned
- Custom wall, ceiling, and lighting layout drawings for selfperform work
- Colored diagrams for precise communication with field
- Contractor adds detail and information to, but doesn't change, architects contract documents





BY RELYING ON 4-D, THE PROJECT TEAM PERFORMED THE NECESSARY LAYOUT AND INSTALLATION FLAWLESSLY AND ON SCHEDULE

- 7 4-D SEQUENCING
- Complex feature stairs with unorthodox sequencing
  - Field welds

     adjacent to
     already-installed
     feature glass
- Integrated models from detailers and subcontractors
- 4-D scheduling in Navisworks "Timeliner"
  - Study and communicate sequencing
  - Optimize schedule
  - Visualize the work



### 8 AUGMENTED REALITY

- Co-locate digital and physical data in single medium
- Craft workers can literally get their heads into virtual details
- Tool to get the richest set of BIM data into the hands of the people who need it the most
- Immediate value
  - Understand proposed design intent
  - Gain confidence to perform the work





### 9 QUALITY CONTROL

- Vela field
  management
  software and
  Navisworks on
  ruggedized tablet
  PC's
- Quality control and verify conditions in the model

#### SAFETY

- Site specific safety plan developed with design background model
- Valuable tool to safely plan hazardous work on roof
- Used at safety orientations





### 10 AS-BUILT DOCUMENTATION

- BIM continuously updated by project team
  - Architects
  - Contractor
    - Subs
- As-built model turned over at project completion
- Navisworks
   selection sets
   used to simplify
   access to
   complex BIM
   database
- Building engineers refer to model to support facilities maintenance

INSTITUTE FOR SYSTEMS BIOLOGY 2012 AIA TAP/ BIM AWARDS



#### BIMFORUM



#### **BIM Award Team Credits**

- Institute for Systems Biology
- Perkins + Will
- BNBuilders

## Institute for Systems Biology

Presented by

Andrew Marsters and Justin Porter | BNBuilders



# Maricopa County South Court Tower


Presented by

John Tocci Jr, Gilbane Companies

The team

- Jim Miller
- Greg Buchanan
- Scott Adams

- Logan Dorrell
- Peter Kennedy
- Sue Klawans




#### problem:


meet a strict schedule and budget without compromising performance






by 15% and deliver the building 18 months early






coordination:
maximize plan
efficiency
through
highly coordinated
multi-use cores


Structure: Brace Frame Coordination

















stems coordination: reduce building area through highly coordinated multi-use cores



















NOT TO SCALE

L SEGMENT C


















#### Architecture & MEP: CFD











#### Architecture & MEP



# Mechanical Platforms




## **Mechanical Platforms**




# MEP: Design Assist Coordination






# Construction: Field BIM







## integrated project delivery



## The Team

## Success is defined by...

- BIM+FM integration that eliminated 2-5 years of building turnover work
- Zero change orders for MEP/FP coordination
- 8 Major BIM-based Prefab Trades
  - Structural Steel, M/P, FP, Electrical, Precast, Curtain Wall, Copper, Detention Systems
- 2,000,000 safe work hours (Gilbane record)
- BIM Enabled Solutions Saved \$30M
- Additionally: Added Scope & Returned Money
  - \$7M in enhanced vertical transportation
  - \$4.75M in contingency returned @ 65% completion

- Accelerated Schedule 18 Months
- Returned Money, Added Scope
- Wasn't a contract requirement

# BIMFORUM



# **Warrior in Transition Barracks**

# Presenters:


David Stone - Mortenson Construction (GC) | Glen Andres - Transystems (Architect)



Warrior In Transition Barracks
Fort Carson, CO

VDC Expedites Soldiers' Road to Recovery









# Project Narrative

The client's program for this barracks facility sought to provide a healing and recuperative environment for wounded soldiers returning from combat, and replace outdated and insufficient facilities currently being used. To meet the rising demand, the team was tasked with the challenge of completing the entire design and construction process within 18 months of project award. Under a traditional construction schedule, much of the structural frame and exterior closure work would be occurring in the middle of the winter months



# Collaborative Design Build Approach





This project exemplifies the team's outstanding BIM technologies to facilitate collaborative project delivery method, while meeting an aggressive design and construction completion schedule. The project was awarded a design-build contract based on bridging "The creative project approach resulted in a

Warrior In Transition Barracks Fort Carson, Colorado

project cost well below

the construction cost

# Benefits and Results:

- A compressed design phase of just 4-1/2 months (vs. 6.5).
- The project was fully enclosed with completed bathrooms in the building just 5 months after foundations.
- General conditions costs were saved by not having to enclose and heat for winter masonry work. Savings we used to provide additional scope in the building.
- Project quality was enhanced. The high quality in the bathrooms and in the precast masonry due to Prefabrication. Punch list was reduced by 50% in comparison to traditional approaches.
- Significant labor was transferred off-site due to prefabrication, reducing the project's safety risk, resulting in an overall project Recordable Injury Rate of 0.83.
- Overall project waste was reduced due to the efficiency of factory processes vs. job-site processes in the precast panels and modular bathrooms.

## Schedule Savings

Design Schedule Savings (Actual vs Typical)



30% Savings

Construction Schedule Savings (Actual vs Contract)



14% Faster

## Sustainability Enhancements

PV Array (added via project savings) Geothermal Field Solar Hot Water

Waste Reduction LED Lighting Energy Modeling

#### Waste Reduction

.65 - WT Barracks

1.0 - Comparable Project

35% Reduction in Landfill Waste

### Energy Modeling (Per SF/ Year)

27Kw/h - WT Barracks 50Kw/h - Comparable

400/ 1------

46% Improvement

## Safety Results

Safety - Recordable Incident Rate (Project vs Contractor vs Industry Average)



39% Improvement

Field Labor Risk Reduction (Drywall/MEP)

## .70 - WT Barracks

1.0 - Comparable Project

30% Improvement

#### Field Punchlist

.50 - WT Barracks

1.0 - Comparable Project

50% Improvement

8878 IIIIpi overnent


Warrior In Transition Barracks Fort Carson, Colorado


# Driving Schedule and Quality - Prefabrication

"Project completed a full 10 weeks ahead of the government's schedule."










# Owner Statement

"...the creation of the model proved to be an invaluable tool during both the design of the facility and then into the construction phase. The model minimized conflicts eliminating related change orders, allowing us to leverage cost saving to upgrade the quality of the project. The contractor used new building methods and superior energysaving design to make this LEED facility a model for others across the Army. The renderings produced from the BIM models were excellent and reflected the true representation of the finished project. They also promoted a real sense of anticipation from soldiers for the completed facility."



# Driving Quality and Sustainability - Precast Walls



Warrior In Transition Barracks Fort Carson, Colorado

# **Architect Statement**

"...the success of the project required utmost commitment from every team member, from the owner's representative, contractor, architect and engineers, product suppliers to the foreman at the site. Having an efficient manner to share and update project information with the entire team was paramount to achieving this success. Our team was able to do that through the innovative use of Virtual Design and Construction. Our Building Information Model provided a collaborative platform to be created and used by all team members within a very short period of time, and conflicts were resolved long before they could hinder the construction schedule."








Warrior In Transition Barracks Fort Carson, Colorado


# Prefabrication Driven Results - Safety







# Warrior In Transition Barracks Fort Carson, CO

# Thank You!







# Warrior In Transition Barracks Fort Carson, CO

VDC Expedites Soldiers' Road to

Recovery









# **Project Narrative**

The client's program for this barracks facility sought to provide a healing and recuperative environment for wounded soldiers returning from combat, and replace outdated and insufficient facilities currently being used. To meet the rising demand, the team was tasked with the challenge of completing the entire design and construction process within 18 months of project award. Under a traditional construction schedule, much of the structural frame and exterior closure work would be occurring in the middle of the winter months.



# Collaborative Design Build Approach





Warrior In Transition Barracks
Fort Carson, Colorado

This project exemplifies the team's outstanding use of BIM technologies to facilitate a collaborative project delivery method, while meeting an aggressive design and construction completion schedule. The project was awarded as a design-build contract based on bridging documents provided by the government.



# **Benefits and Results:**

- A compressed design phase of just 4-1/2 months (vs. 6.5).
- The project was fully enclosed with completed bathrooms in the building just 5 months after foundations.
- General conditions costs were saved by not having to enclose and heat for winter masonry work. Savings were used to provide additional scope in the building.
- Project quality was enhanced. The high quality in the bathrooms and in the precast masonry due to Prefabrication. Punch list was reduced by 50% in comparison to traditional approaches.
- Significant labor was transferred off-site due to prefabrication, reducing the project's safety risk, resulting in an overall project Recordable Injury Rate of 0.83.
- Overall project waste was reduced due to the efficiency of factory processes vs. job-site processes in the precast panels and modular bathrooms.









# **Driving Schedule and Quality - Prefabrication**

"Project completed a full 10 weeks ahead of the government's schedule."









Warrior In Transition Barracks Fort Carson, Colorado

# **Owner Statement**

"...the creation of the model proved to be an invaluable tool during both the design of the facility and then into the construction phase. The model minimized conflicts eliminating related change orders, allowing us to leverage cost saving to upgrade the quality of the project. The contractor used new building methods and superior energysaving design to make this LEED facility a model for others across the Army. The renderings produced from the BIM models were excellent and reflected the true representation of the finished project. They also promoted a real sense of anticipation from soldiers for the completed facility."

# **Prefab Animation**



Warrior In Transition Barracks Fort Carson, Colorado

# **Driving Quality and Sustainability – Precast Walls**



"Reduced Construction time and provided superior quality..."



## Sustainability Enhancements

PV Array (added via project savings) Geothermal Field Solar Hot Water Waste Reduction LED Lighting Energy Modeling

Waste Reduction

.6

.65 - WT Barracks

1.0 - Comparable Project

35% Reduction in Landfill Waste

Energy Modeling (Per SF/ Year)

2

27Kw/h - WT Barracks

50Kw/h - Comparable

46% Improvement

Warrior In Transition Barracks Fort Carson, Colorado

# **Architect Statement**

"...the success of the project required utmost commitment from every team member, from the owner's representative, contractor, architect and engineers, product suppliers to the foreman at the site. Having an efficient manner to share and update project information with the entire team was paramount to achieving this success. Our team was able to do that through the innovative use of Virtual Design and Construction. Our Building Information Model provided a collaborative platform to be created and used by all team members within a very short period of time, and conflicts were resolved long before they could hinder the construction schedule."








Warrior In Transition Barracks Fort Carson, Colorado


# Prefabrication Driven Results - Safety







"Reduced overall schedule and safety risk associated with working at heights on the roof."







Warrior In Transition Barracks Fort Carson, Colorado



# Warrior In Transition Barracks Fort Carson, CO

# **Thank You!**





# BIMFORUM



# BIM Award Team Credits

- 1
- 2
- 3
- 4

# **Warrior in Transition Barracks**

## Presenters:

Mortenson Construction (GC) - David Stone | Transystems (Architect) - Glen Andres

# THANK YOU!!

- BIMForum
- AIA TAP
- COAA
- The Five Finalist Firms!
- YOU!!!

# Acknowledgements









Building what's next.





# VOTE!!! for the Professionals' Choice Award

Go to <a href="http://bit.ly/bimvote">http://bit.ly/bimvote</a>



# VOTE!!! for the Professionals' Choice Award

- Alta Bates Summit Medical Center
- Edith Green-Wendell Wyatt Federal Building Modernization
- Institute for Systems Biology
- Maricopa County South Court Tower
- Warrior in Transition Barracks

