
### **2020 Project Delivery Course**

#### Are You Ready to Design & Build a Field Hospital in 10 Days?





an **AIA** Knowledge Community

November 10, 2020

#### **Moderators**



**GRACE C. LIN, AIA, CSI-CDT** 

CBRE | Healthcare

2019-2020 Chair Project Delivery Knowledge Community Advisory Group



Project Delivery

an **AIA** Knowledge Community



#### **ARLEN SOLOCHEK, FAIA**

**AIA Documents Committee** 

Member

Project Delivery Knowledge Community Advisory Group

### **Project Delivery Case Study Series**

#### Live Course - Are You Ready to Design & Build a Field Hospital in 10 Days?

When: Nov 10, 2020 from 2:00 PM to 3:30 PM (ET) Community: <u>Project Delivery</u>

#### Course 1 = 1.5 LU/HSW

#### Live Course - Project Delivery in a Global Pandemic

When: Nov 12, 2020 from 4:00 PM to 5:30 PM (ET) Community: <u>Project Delivery</u>

#### Course 2 = 1.5 LU/HSW

#### Live Course - COVID-19 Rapid Response Project Delivery

When: Nov 17, 2020 from 4:00 PM to 5:30 PM (ET) Community: <u>Project Delivery</u>

#### Course 3 = 1.5 LU/HSW



Project Delivery

## **AIA/CES Reporting Details**

Your CES credits will be automatically reported given your <u>engaged</u> attendance during the entire event today.

If you are watching in a group setting and have multiple people in the room, please make sure the person who registered for the course, includes your name and AIA member number in their post webinar survey.

We encourage all registrants to fill out the post course survey. Your feedback is important and informs us of future course topics to better meet listener needs.




Project Delivery

### **Questions?**

Submit a question to the moderator via the chat box.

Content-related questions will be answered during the Q&A portion, at the end of the presentation, as time allows. Any questions not answered during Q&A, will be answered and posted online within two (2) weeks.

Tech support questions will be answered by AIA staff promptly.





Project Delivery

# **Copyright notice**

This presentation is protected by US and International Copyright laws. Reproduction, distribution, display and use of the presentation without written permission of the speaker is prohibited.

#### © The American Institute of Architects 2020



Project Delivery

### **Compliance statement**

"AIA Knowledge" is a Registered Provider with The American Institute of Architects Continuing Education Systems (AIA/CES). Credit(s) earned on completion of this program will be reported to AIA/CES for AIA members. Certificates of Completion for both AIA members and non-AIA members are available upon request.

This program is registered with AIA/CES for continuing professional education. As such, it does not include content that may be deemed or construed to be an approval or endorsement by the AIA of any material of construction or any method or manner of handling, using, distributing, or dealing in any material or product.



Project Delivery

#### Project Delivery in COVID-19 Era

"The COVID-19 pandemic is unprecedented. It has pressed on rapid design response and instant construction delivery to serve the community.

The AIA Project Delivery Knowledge Community (PDKC) gathered case studies from a number of architects who worked on the front lines during the public health emergency. These case studies share their stories, what they've experienced and learned in delivering essential projects during the moments of crisis. What worked, traps to avoid, how to win cooperation, and the course of actions taken to successfully deliver the projects.

These case studies highlight architects' work that will inspire and improve the visibility and awareness of project delivery in our profession. Such leadership role demonstrates the importance of project delivery and helps architects rise to the occasion."



The AmericanProject DeliveryInstitutean AIA Knowledge Community

*Grace Lin, AIA Chair of AIA PDKC* 

#### **Presenters**





LYNN M. EWING, PE

Contracting Officer's Representative USACE, Chicago District

#### PAUL WIDLARZ, AIA Principal

HGA

CORY POWERS Engineering Principal HGA **ADAM JELEN** Senior Vice President, Midwest Division Gilbane Building Company



Project Delivery

## Learning objectives

- 1. How to build a high-performing rapid response team
- 2. Assembling the ultimate "Big Room"
- How to convert an expo hall into a field hospital strategies & tactics
- 4. Unique considerations when designing a field hospital in a prison





### Our Mission...

- Convert an exposition hall into an Alternate Care Site (ACS)
  - 296 Beds (in-line O2), 234 beds (bottled O2), 234 future beds
  - Temporary/portable support areas (toilets/showers/hand-washing)
  - Temporary medical gas (O2) facilities
  - Infrastructure (HVAC, Electrical, IT, Fire Protection) to support
- 10 days to complete
- Ability to demobilize without a negative impact on facility



Project Delivery

#### Building the Team


OEquip

INCLUS

NES.

#### **Operation Enduring Health – COVID-19 Response – USACE Chicago District**

Summary of project life cycle





Project Delivery

## Initiation

- Market research determine pre-selected pool of contractors
- Survey of potential sites as requested by the state
- State development of the resource requirements submitted to FEMA
- Awarding of the MATO (mission assignment task order) from FEMA
- Development of the PWS (performance work statement)
- Issuance of solicitation and source selection board
- Right of entry from state
- Award of undefinitized design-build letter contract
  - Durations, vision of USACE, requirements
  - Flow chart



Project Delivery

## **Planning & Execution**

- Planning phase began upon award
- Kickoff meeting with all stakeholders, prime contractor and subcontractors
- Execution began upon award





# **Assembling the Design-Build Team**

- Trusted and proven partners
  - Design team
  - Subcontractor (trade partners)
- Federal experience
- Local resources and knowledge (AHJ's, supply chain, workforce, etc.)
- Ability to prefabricate
- Ability to deliver senior leadership on site to boots on the ground
- Training and set expectations for the team



Project Delivery

# Team Building & Culture

- Daily presentation and collaboration
- Starting with caring moment
- Commitments and decisions
- Team building activities and appreciation Deliver on our Mission **TOGETHER**





### **Building the Design Team**

"We didn't design and build this in 10 days, we designed and built this in 25 years plus 10 days..."








Project Delivery

#### **Converting an Expo Hall into a Field Hospital**



### **Overall Timeline**




Day 1 - 0800 Mobilize & Kick-Off Day 1 - 1600 Layout Concept Defined Day 1 - 2000 Partitions Released

Day 2 - For Information Set of Documents Completed Day 2 - Critical Materials Procured Day 2 - Construction Started




Day 3 – Sign-off for Information Documents Day 3 – MEFP Rough-in and Distribution, Partitions Delivered and Install Started



Day 4 – Partition Installation, Wall Framing, MEFP Rough-in and Install





an **AIA** Knowledge Community



Day 6 – Major Equipment Deliveries, East Site Construction, **Closeout and Transition Process Underway** 



Day 7– Major Equipment Deliveries, North and East Site construction, Closeout and Transition Process Underway



Day 8 – Technology Systems, Wrap-up construction, Closeout-Commissioning and Testing Process Underway



Day 9 - Complete Punchlist Work, Final Cleaning, AHJ Inspections, Deliver Closeout Documents



Day 10 - Complete Cleaning and Punchlist Items, Demobilization, Lessons Learned and Team Appreciation

#### A Video Overview...

## **On-Boarding**...

- Received meeting appointment for following morning at 0800
- Early days of the pandemic where we were from a COVID knowledge standpoint at that time was very different from now










# **Kick-Off Meeting**

- Work Scope (PWS)
- Preliminary floor plan
- Facility tour
- 1<sup>st</sup> deadline final floor plan 1600 hrs








#### Wisconsin State Fair Grounds

West Allis, Wisconsin








# **Key Stats**

- Exposition Hall
- Built in 2002
- Multiple entries all sides
- Loading dock
- Columns 90' on center
- Utility boxes 30' O.C.










#### State of Wesser State of Wesser For Parkee Col. REishers ACE Support Team PartAgen & Planning Team

### rhe Ultimate Big Room

IR PAR



SECOND FLOOR


# **Monitoring & Control**

- Daily progress meetings with all stakeholders, daily construction meetings
- Daily reporting on actual expenses
- Daily reporting on safety and quality control
- Design submittals for information only
- Request for Information (RFI)'s responded to immediately
- Definitization of contract



Project Delivery

#### Design Process The Triple Aim





Project Delivery

### **Design Process** – **Operational Flows**

- Patient flow
  - Accessing the facility
  - Movement within the facility
- Staff flow
  - Building access
  - Movement within facility
- Material flow


Architects

 How do goods arrive and move through the facility




**Project Delivery** 










#### **Patient Intake Flow**

- 1. Ambulance drop off
- 2. Registration desk
- 3. Nurse station for room assignment
- 4. Transport patient to "room"

#### STATE FAIR PARK ALTERNATE CARE FACILITY 640 S 84TH ST., WEST ALLIS, WI

HGA

333 East Erie Street Milwaukee, Wisconsin 53202 Telephone 414.278.8200




THEREBY CERTIFY THAT THIS PLAN, SPECIFICATION OR REPORT THIS PREVATED BY MILOG UNDER MY DIRECT SUPERVISION AND THAT I MA A DULY UCDISED AND ITECT UNDER THE LIAWS OF THE STATE OF

	ACTI	
1GA I	NU:	3099-005-0
IGA	SSUANCE HISTORY - T	HS SHEET
_		
_		
-		
_		
_		

COPYRIGHT HAMMEL GREEN AND ABRAHAMSON IN

### **Patient Care Areas**




#### Planning Guiding Principles:

#### Patient safety

- Maximize visibility
- Minimize potential hazards
- Minimize walking distances
  - Caregivers
  - Patients (toilet rooms)
- Clear wayfinding
- Centralized support functions
- Efficient wall layout with access to utilities
- ADA accessibility
- Best value
- Supports prefabrication



Project Delivery



#### Hall A – 296 Beds

- 28 beds in rows A & B to provide additional space at entry
- Remaining rows have 30 beds row
- 12 patient toilets with additional toilets for staff use in NE corner

HGA

333 East Erie Street Milwaukee, Wisconsin 5320 Telephone 414.278.8200

STATE FAIR PARK

ALTERNATE CARE FACILITY

HGA NO

ES

S

0

AC

OR

3099-005-00

PLAN

ACTIVATION

NOT TO SCALE

DATE: APRIL 13, 2020

"FOR INFORMATION"


AP01

DESIGN

COPYRIGHT

640 S 84TH ST.

WEST ALLIS W




- **CORRIDOR B**
- THERE IS NO ROW "I" TO ELIMINATE CONFUSION











#### STATE FAIR PARK ALTERNATE CARE FACILITY 640 S 84TH ST., WEST ALLIS, WI

HGA


333 East Erie Street

Milwaukee, Wisconsin 5320 Telephone 414.278.8200


I HEREBY CERTIFY THAT THIS PLAN. SPECIFICATION OR REPORT WAR PREPARED BY ME OR UNDER MY DREICT SUPERVISION AND THAT I AM A DULY LICENSED ARCHITECT UNDER THE LIANS OF THE STATE OF

#### **Staff Entry Flow**

- 1. Staff check-in and receive assignments from admin area at the concession stand
- 2. Staff proceed to donning area, gather PPE supplies
- 3. Change in changing rooms
- 4. Lock up personal items in lockers
- 5. Enter Hall 'C' via the ante room







ŝ S 0 3099-005-00 ACTIVATION PLAN NOT TO SCALE DATE: APRIL 13, 2020 DESIGN AC "FOR INFORMATION" OR **AP01** 

теленсениен АР01

STAFF EXIT HALL 'C' 234 BEDS

HALL 'B' STAFF


234 BED

HALL 'A' 296 BEDS

FACILITY

640 S 84TH ST.

WEST ALLIS W









**East Dock Electrical Distribution** 





**Electrical Systems Prefabrication Delivery and Installation** 









**Oxygen Systems Prefabrication Delivery and Installation** 

## Close Out and Operation & Maintenance (O&M)

- State representatives and clinicians need to be part of pre & final inspections
- Integration of new team into facility
- As-built drawing review
- Turnover letter to State
- Operations & Maintenance (O&M)
  - Not responsibility of USACE or contractor but Wrap Around Service
  - Warranties limited to manufacturer warranties on new equipment; no warranties on construction



Project Delivery

## Lessons Learned – Hot Wash

#### Teamwork

- Assemble trusted, highly-qualified and hard-working partners
- Bring all key stakeholders into the Big Room (face-toface and on-site)
  - USACE
  - Building Owner (Leaders & Facilities Team)
  - Healthcare provider
  - Government officials
  - AHJ's
  - Construction Manager
  - A&E Designers
  - Trade Partners
- High energy level and excitement from the team.
- Open line of communication with all parties
- Provide DM's with the information needed to make decisions quickly
- Take a breath and pause for a moment to plan the work flow
- Assign 1 content manager from each team.....Ben, Matthew...



Project Delivery

an **AIA** Knowledge Community

#### Design

- Lead with Strategy review operations plan with Operators to understand their process flow to develop the program
- Ask the right questions.
- Determine the high-level flows (Patient, Staff and Materials) Develop an efficient logical plan that responds to operations quickly & distribute to the team
- Leverage ALL the talent in the room (Architects, Engineers, Construction Manager, Trades)
- Past working relationships key (Gilbane, HGA, Ahern, Staff)

#### **Lessons Learned**

#### Tools

- Use MS Teams to track tasks due (ASI, Punchlist, As-builts, Etc.)
- Plan the deliverable schedule with a QC check
- We needed a shared folder on a cloud network. Relying on people to forward emails is too risky
- Implement commissioning earlier to test existing HVAC equipment
- HGA's iPad based punchlist tool was great.
- Drone footage was valuable

#### Details

- Add electrical panel/clearance to backgrounds
- Earlier interior elevation of Patient Room & other key spaces
- Earlier Site drawing. Focused team on this topic
- Consider ceilings in soiled utility rooms.
- Room Numbering & Signage
- Use Revit
- Develop headwall earlier than prefab starts
- Solid existing drawings.... On other projects this was a huge problem out of the gate





#### **Converting a Prison into a Field Hospital**



## **Our New Mission...**


- Convert existing prison facility into an Alternate Care Site (ACS)
  - 30 bed dorm low acuity (inline O2), 90 beds non acute (no O2)
  - Temporary medical gas (O2) facilities
  - Infrastructure (HVAC, Electrical, IT, Fire Protection) updates
- Staff support areas medical and correction officers
- 20 days to complete



Project Delivery

# (Re)Assembling the Team

- Added corrections experience
- Integrated lessons learned







## **Team Caring Moment**

## **Authorities Having Jurisdiction**

USACE - Contracting Officer's Representative (COR) - Mr. Robert Vanoer - Scope Direction | Approval | Administration

Milwaukee County - Emergency Management Director - Ms. Christine Westrich

State of Wisconsin - Director of Detention Facilities - Mr. Gregory Bucholtz Plan Review and Letter 5/4 Final Inspections Team

City of Franklin - Building - Building Permit and Inspection(s) - Mr. Scott Satula Demolition Permit 5/3 Building Permit 5/6 (USACE Letter + Stamped Drawings) General Inspections and Final Inspection Team

**City of Franklin - Fire** (Fire Suppression | Fire Alarm) - Mr. Adam Remington Final Inspections Team


**City of Franklin - Health Services** 

**Final Inspections Team** 



Project Delivery

an **AIA** Knowledge Community



Cc:

## **Kick-Off Meeting**

- Work scope (PWS)
- Preliminary floor plan
- Facility tour





an **AIA** Knowledge Community

Performance Work Statement (PWS)

Convert an Open Area Dormitory within the Secured Correctional Campus into a Non Acute COVID Patient Care Facility

**Target Audience:** Two categories of patient spaces will be at the site. FPA 99 Category 3 Patient, which is defined as patient care "activities in which the failure of equipment or a system is not likely to cause injury to patients, staff, or visitors but can cause discomfort" (NFPA 99 para. 4.1.3). [only 1 category identified]

#### 1.0 GENERAL

This PWS provides minimum criteria for "sufficiency of care" to provide a rapid response to the expected need, therefore, it is critical that local authorities and/or Area Fire Marshal are involved in the development of the design and acceptance of this temporary Alternate Care Facility site.


The Coronavirus disease 2019 (COVID-19) is a respiratory infection caused by newly emergent coronavirus first recognized in Wuhan, China in December of 2019. For the purpose of this document. Non-acute COVID-19 patients are defined as <u>those patients that do not require a</u> <u>ventilator, but may require oxygen (i.e. the use of either nasal tube or mask)</u> and do require nursing support.

The Contractor shall retrofit the selected space into a Temporary Alternate Care Site (ACS) serving primarily non acute COVID-19 patients plus some low acute COVID-19 patients in transition to a medical facility which supports higher acuity care.

Standard dormitory layouts provide for 32 beds spaces each. The Contractor will not provide beds. Dormitory infrastructure has many built-in fire protection and life safety safeguards. The existing emergency duty generator shall be tested and repaired as required along with essential power circuits to ensure that uninterrupted power is available at all times. Submit the report to the COR within 24 hours of completing the test. All plumbing fixtures will be inspected and all brought up to full functioning performance.

Within the Lotter Building the Contractor shall convert three (3) open dormitory areas of approximately 2500 sf each (including toilet and shower facilities), support areas such as the Dining room (room 130), and other support areas into a non-acute infectious COVID-19 patient care facility based on the requirements of NFPA 99 Space Category 3 (Basic Care).


The Contractor shall convert one (1) open dormitory area of approximately 2500 sf (including toilet facilities) into a low acute infectious COVID-19 patient care facility based on the requirements of NFPA 99 Space Category 3 (Basic Care). A centralized oxygen distribution system will be provided. Oxygen dispensing shall be provided at a minimum volume flow rate of 6 liters per minute at the outlet for each of the 32 patient's beds. Other medical gas systems, such as medical grade air or vacuum lines, will not be provided.


















## **Overall Timeline**







### **Big Room Re-Imagined**






Project Delivery


## **Design Process**


- Patient/inmate flow
  - Accessing the facility
  - Movement within the facility
  - Security and safety
- Staff flow
  - Building access
  - Movement within facility
  - Patient observation and interaction
  - Safety
- Material flow
  - How do goods arrive and move through the facility





Project Delivery





























## **Overall Keys to Success**

- 1<sup>st</sup> 48 hours and with value decisions
- Coming in with a proven robust local team
- On site leadership from each partner
- Clear critical path for each day and shift to include design, procurement, decisions, close out and AHJ's + user
- Daily leadership meetings with follow-up
- Great team spirit and a high bar set each day

- Moments of pride
- Diversity of great talent by all partners on site
- Project controls management and position
- The right players at table from day one
- Total project life cycle management and care by team, selflessness



Project Delivery

### COVID-19 Rapid Response Project Delivery Case Studies





The American Institute of Architects Project Delivery

## AIA KnowledgeNet

https://network.aia.org/communities

The AIA **Project Delivery Knowledge Community** (PDKC) promotes the architect's leadership role in all project delivery methods by assembling and distributing knowledge and best practices for a variety of project delivery methods, e.g. design-build (DB), integrated project deliveries (IPD), and public-private partnerships (P3).



Project Delivery

### **Upcoming Courses**

#### November 2020

Live Course - Project Delivery in a Global Pandemic

When: Nov 12, 2020 from 4:00 PM to 5:30 PM (ET) Community: <u>Project Delivery</u>

#### 1.5 Hours Course = 1.5 LU/HSW

#### Live Course - COVID-19 Rapid Response Project Delivery

When: Nov 17, 2020 from 4:00 PM to 5:30 PM (ET) Community: <u>Project Delivery</u>

#### 1.5 Hours Course = 1.5 LU/HSW

Visit <a href="https://network.aia.org/projectdelivery">https://network.aia.org/projectdelivery</a> for more information



Project Delivery

# THANK YOU



