2020 Project Delivery Course

Covid-19 Rapid Response Project Delivery



Moderators



GRACE C. LIN, AIA, CSI-CDT

CBRE | Healthcare

2019-2020 Chair Project Delivery Knowledge Community Advisory Group



GREG GIDEZ, AIA, FDBIA, LEED AP
Hensel Phelps

Member
Project Delivery Knowledge
Community Advisory Group



Project Delivery

Project Delivery Case Study Webinar Series

<u>Live Course - Are You Ready to Design & Build a Field Hospital in 10 Days?</u>

When: Nov 10, 2020 from 2:00 PM to 3:30 PM (ET)

Community: Project Delivery

Course 1 = 1.5 LU/HSW

Live Course - Project Delivery in a Global Pandemic

When: Nov 12, 2020 from 4:00 PM to 5:30 PM (ET)

Community: Project Delivery

Course 2 = 1.5 LU/HSW

Live Course - COVID-19 Rapid Response Project Delivery

When: Nov 17, 2020 from 4:00 PM to 5:30 PM (ET)

Community: Project Delivery

Course 3 = 1.5 LU/HSW



AIA/CES Reporting Details

Your CES credits will be automatically reported given your <u>engaged</u> attendance during the entire event today.

If you are watching in a group setting and have multiple people in the room, please make sure the person who registered for the course, includes your name and AIA member number in their post webinar survey.


We encourage all registrants to fill out the post course survey. Your feedback is important and informs us of future course topics to better meet listener needs.

Questions?

Submit a question to the moderator via the chat box.

Content-related questions will be answered during the Q&A portion, at the end of the presentation, as time allows. Any questions not answered during Q&A, will be answered and posted online within two (2) weeks.

Tech support questions will be answered by AIA staff promptly.





Copyright notice

This presentation is protected by US and International Copyright laws. Reproduction, distribution, display and use of the presentation without written permission of the speaker is prohibited.

© The American Institute of Architects 2020



Compliance statement

"AIA Knowledge" is a Registered Provider with The American Institute of Architects Continuing Education Systems (AIA/CES). Credit(s) earned on completion of this program will be reported to AIA/CES for AIA members. Certificates of Completion for both AIA members and non-AIA members are available upon request.

This program is registered with AIA/CES for continuing professional education. As such, it does not include content that may be deemed or construed to be an approval or endorsement by the AIA of any material of construction or any method or manner of handling, using, distributing, or dealing in any material or product.



Project Delivery in COVID-19 Era

"The COVID-19 pandemic is unprecedented. It has pressed on rapid design response and instant construction delivery to serve the community.

The AIA Project Delivery Knowledge Community (PDKC) gathered case studies from a number of architects who worked on the front lines during the public health emergency. These case studies share their stories, what they've experienced and learned in delivering essential projects during the moments of crisis. What worked, traps to avoid, how to win cooperation, and the course of actions taken to successfully deliver the projects.

These case studies highlight architects' work that will inspire and improve the visibility and awareness of project delivery in our profession. Such leadership role demonstrates the importance of project delivery and helps architects rise to the occasion."



2020 Project Delivery Course

Covid-19 Infrastructure in Low Resource Settings



Presenters



Gerard Georges
Director of
Architecture
Build Health
International



Thomas Darr
Project Architect &
Site Supervisor
Build Health
International



Architectural
Designer
Build Health
International



Learning Objectives

- Understand basic design principles for infection control in healthcare settings
- Learn principles of material selection options for safe, rapid construction in low resource settings
- 3. Learn about international remote construction administration during a global health crisis
- 4. Understand the role sustainable systems play in areas with limited infrastructure; ie. water, energy

Course Description

This webinar will investigate the process of designing and implementing expanded hospital capacity in low resource settings throughout the world. While cities like Boston were able to construct massive, high quality medical facilities rapidly and with access to a variety of building materials and professionals, communities in Haiti and Uganda had to respond with the same urgency but far fewer resources. Build Health International used its experience working in these settings combined with medical expertise from Ebola and other outbreaks to design and construct Covid-19 treatment centers with all the constraints associated with building in developing nations.



Agenda

- Background
- Design Considerations
- · Computational Fluid Dynamics (CFD) Analysis
- Construction Process
- Impact

Build Health International - Why we exist

BHI promotes health equity by developing high-quality health infrastructure to enable access to dignified and affordable healthcare in impoverished and resource-constrained regions of the world.












Port Loko Government Hospital, Labor & Delivery, Sierra Leone







Building in Low Resource Settings

High Resource

- Widely available trained, licensed labor
- □ High quality materials readily available
- Well established medical supply chains

Low Resource

- Little access to trained labor but lots of untrained workers
- □ Limited access to high quality materials
- □ Poor or non-existent medical supply chains


Covid-19 Treatment Center Design

Covid-19 Treatment Center Design Considerations

- Patient & Staff Safety
- Separation of Covid-19 patients from hospital population
- Protection for doctors & staff
- Airflow & ventilation to remove contaminated air
- Flexibility of application



Treatment Center Prototype Campus Plan for Sites with Testing



Staff Building

The staff building is designed as an integrated workroom, with don and doff spaces. This model should be used for sites with multiple COVID-19 wards within a Coronavirus Treatment Center. See full construction drawings an alternative ward design with in-ward donning and doffing areas.

In order to facilitate unidirectional flow of staff and materials, the staff building should be constructed on the outer fence line, such that the donning entrance and the doffing exit should face the outside of the treatment center site.

A staff sanitary block (including shower, toilet, and sink) should be constructed or made available near the staff building, but outside the treatment center.




TREATMENT CENTER PERIMETER FENCE Staff Flow No Covid Covid Suspect DON Covid Confirmed D1-1 STAFF FENCE BETWEEN WORK SUSPECT AND D1-2 CONFIRMED AREAS [TESTING SITES ONLY] DOFF D1-3 TREATMENT CENTER PERIMETER FENCE D1 - LAYOUT

SCALE 1:100

Build Health International

Construction Document Set



1S1 - LAYOUT

SCALE 1:100




SUSPECT WARD 1 DESCRIPTION

SUSPECT WARDS SHOULD BE USED FOR THE FOLLOWING PATIENTS:

- PATIENTS WHO HAVE BEEN CLINICALLY DIAGNOSED AS COVID POSITIVE
- PATIENTS WHO HAVE BEEN TESTED AND ARE AWAITING RESULTS


SUSPECT WARDS ARE DISTINGUISHED BY WIDER BED SPACING AND DIVIDER PANELS BETWEEN BEDS TO PROTECT PATIENTS WHO MAY NOT HAVE COVID FROM NOSOCOMIAL SPREAD.

SUSPECT WARD 1 INCLUDES STAFF DON & DOFF ROOMS. THIS IS RECOMMENDED ONLY IN AREAS WHERE ONE OR TWO WARDS ARE CONSTRUCTED. FOR FACILITIES IN WHICH MORE THAN TWO WARDS ARE CONSTRUCTED, REFER TO SUSPECT WARD 2, WHICH IS DESIGNED TO BE ACCOMPANIED BY CENTRAL DON & DOFF SPACES.



SCALE


S1-01 WARD S1 OVERVIEW 5/14/2020 3:32:59 PM



1S1 - CONSTRUCTION PLAN

SCALE 1:100







2 S1 WARD CEILING PLAN

SCALE 1:100

S1-02




1 S1 SHORT SECTION SCALE 1:50





2 S1 LONG SECTION


SCALE 1:50















SCALE 1:100

S1-04 WARD S1 ELEVATIONS



RECEPTACLE MOUNTED 1.12M AFF LIGHT SWITCH MOUNTED 1.12M AFF \$ FC FAN CONTROL MOUNTED 1.12M AFF HANGING LED LIGHT L-1 CF-1 VARIABLE SPEED CEILING FAN WS-1 LED WEATHERPROOF WALL SCONCE **ELECTRICAL LEGEND**




1S1 - POWER PLAN

SCALE 1:100



2 S1 LIGHTING PLAN SCALE 1:100



Ventilation & CFD Analysis

Goal for 12 ACH but very little access to mechanical systems

Windows and interior fans provide natural ventilation


Dividers between beds help reduce airflow between patients

Computational Fluid Dynamics analysis was used to confirm airflow predictions




AIR CHANGES - CFD MODEL SETUP

Setup of CFD model to study passive ventilation at St. Boniface test site in Fond des Blancs, Haiti.




Material Model









Local Wind Direction and Magnitude - Fond des Blancs, Haiti

Solver: Autodesk CFD

Turbulence Model: k-epsilon
Turbulent/Laminar: Turbulent


Turb/Lam Ratio: 100


Compressibility: Incompressible

Gravity: 0,0,-1

AIR CHANGES - VALIDATION

We validated our air changes per hour metric by comparing results from the Autodesk CFD simulation model to ACH figures found in the example ward design of the referenced WHO document.






https://www.ncbi.nlm.nih.gov/books/NBK143284/


Air Changes per Hour		
	Adesk CFD	WHO Baseline
Open window (100%) + open door	36.82	37
Open window (50%) + open door	25.58	28
Open window (100%) + closed door	4.27	4.2

*CFD simulation matches results from WHO reference formula.


AIR CHANGES - COVID WARDS DESIGN ANALYSIS

We then studied the air changes per hour in the three prototype COVID ward designs. Three typical wind velocities from Fond des Blancs climate data are simulated. The baseline of 12 ACH is met in these three cases given the simulation model conditions outlined in slide 3.









Ward B - Interior partitions

the second secon
111
The state of the s
Marie Marie
the second second
The second second
The same of the sa
and the second s
IN THE PARTY AND ADDRESS OF THE PARTY AND ADDR

Ward C - Interior partitions + fans

	ACH Avg Wind (3.6 m/s)		ACH Min Wind (1.8 m/s)
Ward A	18.7	37.6	17.4
Ward B	19.3	37.7	16.6
Ward C	25.1	39.3	14.6



Natural Ventilation

Opportunities for further studies

Combine solar gain and air flow analysis

- Integrate with solar studies for specific weather systems

Air flow analysis for multiple wind directions

Air flow analysis for alternate interior configurations

Exhaust alternatives

Airflow impact due to site obstructions



Covid-19 Treatment Center Construction

Construction Process

No construction supervisors on site due to Covid-19

Remote construction administration from BHI home offices

On-the-ground crew in Haiti trained on previous projects

Photo-based guide for construction





1: Site Clearing



2: Concrete Forming



3: Concrete Pouring



4: Wall Framing



5: Stand Up Walls



6: Sheath Walls





7: Assemble Trusses



8: Paint Trusses



9: Paint Walls



10: Place Trusses



11: Bolt Truss Plates



12: Install Purlins





13: Insulate Roof



14: Install Roofing



15: Install Electricity



16: Plastic Interior



17: Sink & Workstation




18: Clean
















Impact

50 beds in Fond des Blanc, Haiti

116 beds in Mbarara, Uganda

100 beds in Mirebalais, Haiti









2020 Project Delivery Course

From Surge to Solution: How Northwell Health Rapidly Built a COVID-19 Surge Unit



Presenters



Thomas Morris
Partner

E4H Environments for Health Architecture



Alexandra Vigliarolo, RA
Project Manager
Northwell Health



Learning Objectives

- 1. Attendees will be able to identify strategies for designing an adaptable patient environment to address the unknowns of a pandemic disease.
- 2. Attendees will learn tactics for rapid project implementation with a multidisciplinary team, while working in a remote working environment.
- 3. Attendees will understand challenges and solutions for obtaining construction materials in periods of high demand.
- 4. Attendees will review regulatory and code applications, and best practices in the rapid deployment of pandemic project solutions.

From Surge to Solution

AGENDA

- Overview & Relationship
- The Need
- The Opportunity
- Project & Delivery
- Challenges
- Construction Process
- Lessons Learned & Solutions




Project Delivery

an **AIA** Knowledge Community








NYC Faces a Patient Surge

New York Passes 250,000 COVID-19 Cases

Cumulative number of confirmed COVID-19 cases in selected U.S. states (March 16 - April 20)







The Need

- Dedicated System-Wide COVID-19 Unit
- Aleve Emergency Department Surge
- Isolate Positive Patients
 - 60-65 Beds
 - Ward Configuration
 - 9,100SF Available
 - Negative Pressure
 - Emergency Power
 - Medical Gases Oxygen, Vacuum, Medical Air
 - Handwashing Stations
 - Small Pharmacy/Clean Supply/Soiled Utility
 - Telemetry at Every Bed









The Opportunity





Design Process


- 12,500SF total space
- Input from Nurse management
- Daily Zoom meetings
- Codes & Guidelines
- Concessions
- "Unofficial" moratorium
- "Eyes in the field"



Project Delivery
an **AIA** Knowledge Community








09 April 2020

Challenges

- Emergency Power
- Oxygen
- Medical Gases
- HVAC/Exhaust
- No major building Shut-Downs





Construction Process

- 3 weeks to delivery
- Workforce Shortage
- Materials shortage
- COVID
 Construction
 Protocols





Lessons Learned & Solutions

- We needed dedicated circuits at each bay for a ventilator at each bed.
- As the numbers increased it became clear that dialysis patients were common among the infected COVID-19 patients so we had to install hookups for dialysis machines at 8 beds a few days before we opened.
- We added day 2 work including a break room and bathroom for staff so they didn't have to leave the space to take a break and possibly infect other areas.
- In order to keep costs and amount of work down we put all lights on the same switches. Once the space was open for a week or two we became aware of the fact that during the night shifts, the patients couldn't sleep well with all the lights while still allowing the nursing staff to do their jobs. We had electricians in full PPE working around patients to add switches to allow for less light at night.
- The space was originally designed for office space, not a heavily populated ICU with a lot of equipment so the cooling system was not equipped to handle the space. It was uncomfortably hot for staff inside the space so we added some spot coolers.







AIA KnowledgeNet

https://network.aia.org/communities

The AIA **Project Delivery Knowledge Community** (PDKC) promotes the architect's leadership role in all project delivery methods by assembling and distributing knowledge and best practices for a variety of project delivery methods, e.g. design-build (DB), integrated project deliveries (IPD), and public-private partnerships (P3).



Upcoming Course

December 2020

<u>Live Course - Virtual Design + Construction: The Future of Project Delivery</u>

When: Dec 8, 2020 from 2:00 PM to 3:00 PM (ET)

Community: Project Delivery

1.0 Hour Course = 1.0 LU

Visit https://network.aia.org/projectdelivery for more information

THANK YOU

